2009 AERIAL PHOTOGRAPHY

EXISTING CONDITIONS & PAVEMENT MARKINGS

EXISTING CONDITIONS
COGSWELL TO DUKE ST.

EAST SIDE
11 – EVENING/WEEKEND PARKING SPACES
11 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
7 – EVENING/WEEKEND PARKING SPACES
4 – LOADING SPACES (ANYTIME)
4 – LOADING PERMITTED (5AM–4PM)

EXISTING CONDITIONS
DUKE ST. TO GEORGE ST.

EAST SIDE
14 – EVENING/WEEKEND PARKING SPACES
14 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
5 – METERED PARKING SPACES
5 – LOADING SPACES (ANYTIME)

EXISTING CONDITIONS
GEORGE ST. TO PRINCE ST.

EAST SIDE
15 – EVENING/WEEKEND PARKING SPACES
15 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
3 – METERED PARKING SPACES
5 – LOADING SPACES (ANYTIME)
5 – BUS STOP

EXISTING CONDITIONS
PRINCE ST. TO SACKVILLE ST.

EAST SIDE
11 – EVENING/WEEKEND PARKING SPACES
2 – LOADING SPACES (ANYTIME)
11 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
3 – METERED PARKING SPACES
1 – 3HR ACCESSIBLE PARKING
1 – LOADING SPACE (ANYTIME)
2 – TAXI STAND SPACES

EXISTING CONDITIONS
SACKVILLE ST. TO SALTER ST.

EAST SIDE
20 – METERED PARKING SPACES
2 – LOADING SPACES (ANYTIME)
20 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
3 – METERED PARKING SPACES
1 – 3HR ACCESSIBLE PARKING
7 – LOADING SPACES (ANYTIME)
1 – BUS STOP

EXISTING CONDITIONS
SALTER ST. TO BISHOP ST.

EAST SIDE
6 – METERED PARKING SPACES (5AM–4PM)
6 – 2 HR PARKING SPACES
11 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
5 – METERED PARKING SPACES
1 – 2 HR ACCESSIBLE PARKING
10 – LOADING SPACES (ANYTIME)
1 – BUS STOP

EXISTING CONDITIONS
BISHOP ST. TO MORRIS ST.

EAST SIDE
6 – 1 HR PARKING SPACES
7 – LOADING SPACES (ANYTIME)

WEST SIDE
4 – METERED PARKING SPACES
1 – 2 HR ACCESSIBLE SPACE
10 – LOADING SPACES (ANYTIME)
1 – BUS STOP

EXISTING CONDITIONS
MORRIS ST. TO TERMINAL RD.

EAST SIDE
13 – METERED PARKING SPACES
2 – 2 HR ACCESSIBLE SPACES
2 – LOADING SPACES (ANYTIME)

WEST SIDE
13 – METERED PARKING SPACES
2 – 2 HR PARKING SPACES
7 – LOADING SPACES (ANYTIME)

PROPOSED CONDITIONS & PAVEMENT MARKINGS

PROPOSED STREET MARKINGS
COGSWELL TO DUKE ST.

EAST SIDE
11 – EVENING/WEEKEND PARKING SPACES
11 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
4 – LOADING SPACES (ANYTIME)
BIKE LANE – NO STOPPING ANYTIME

PROPOSED STREET MARKINGS
DUKE ST. TO GEORGE ST.

EAST SIDE
14 – EVENING/WEEKEND PARKING SPACES
14 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
BIKE LANE – NO STOPPING ANYTIME

GEORGE STREET
6 – LOADING SPACES (PROVISIONAL)

PROPOSED STREET MARKINGS
GEORGE ST. TO PRINCE ST.

EAST SIDE
6 – METERED PARKING SPACES (5AM–4PM)
14 – EVENING/WEEKEND PARKING SPACES
8 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
BIKE LANE – NO STOPPING ANYTIME
1 – BUS STOP
1 – AMBASSADOR BUS TOUR STOP (SEASONAL)

PRINCE STREET
2 – TAXI STAND SPACES
(RELOCATED FROM HOLLIS ST.)

PROPOSED STREET MARKINGS
PRINCE ST. TO SACKVILLE ST.

EAST SIDE
3 – 3 HR ACCESSIBLE PARKING (5AM–4PM)
8 – EVENING/WEEKEND PARKING SPACES
8 – LOADING PERMITTED (5AM–4PM)
8 – LOADING PERMITTED (5AM–4PM)

WEST SIDE
BIKE LANE – NO STOPPING ANYTIME

PROPOSED STREET MARKINGS
SACKVILLE ST. TO SALTER ST.

EAST SIDE
14 – METERED PARKING SPACES
3 – 3 HR ACCESSIBLE PARKING (5AM–6PM)
3 – EVENING/WEEKEND PARKING SPACES
4 – LOADING SPACES (5AM–6PM)

WEST SIDE
BIKE LANE – NO STOPPING ANYTIME
1 – BUS STOP

PROPOSED STREET MARKINGS
SALTER ST. TO BISHOP ST.

EAST SIDE
15 – METERED PARKING SPACES
5 – LOADING SPACES (ANYTIME)

WEST SIDE
BIKE LANE – NO STOPPING ANYTIME
1 – BUS STOP

PROPOSED STREET MARKINGS
BISHOP ST. TO MORRIS ST.

EAST SIDE
6 – METERED PARKING SPACES
2 – 2 HR ACCESSIBLE SPACES
2 – LOADING SPACES (ANYTIME)

WEST SIDE
BIKE LANE – NO STOPPING ANYTIME
1 – BUS STOP

PROPOSED STREET MARKINGS
MORRIS ST. TO TERMINAL RD.

EAST SIDE
13 – METERED PARKING SPACES
2 – 2HR ACCESSIBLE SPACES
2 – LOADING SPACES (ANYTIME)

WEST SIDE
13 – METERED PARKING SPACES
4 – LOADING SPACES (ANYTIME)
BIKE LANE – NO STOPPING ANYTIME

KEY PLAN

EXISTING CONDITIONS PROPOSED CONDITIONS

TYPICAL INTERSECTION PAVEMENT MARKINGS



NOTES

1. ALL METERS ARE 90 MINUTE (MON–FRI) UNLESS OTHERWISE INDICATED ON PLAN.

REVIEWED AND APPROVED FOR TRAFFIC TECHNICAL AND PLANNERY AMENDMENTS

Date: _____ Traffic Authority: _____ Date: _____

No.	Date	Revision	Drawn	Appr'd
1		ISSUED FOR CONSTRUCTION		
2		ISSUED FOR TENDER		
3		ISSUED FOR PAVEMENT DESIGN REVIEW		
4		ISSUED FOR REVIEW		

DRAFT COPY

HALIFAX REGIONAL MUNICIPALITY

HOLLIS STREET
COGSWELL TO SOUTH STREET
HALIFAX – WEST REGION

PAVEMENT MARKINGS/BIKE LANE MARKINGS
PROPOSED BIKE LANE

14-XXX

Scale: 1:500 (ANSI B) 1:1000 (ANSI D)
Drawn: JR
Checked: _____
Survey No: ER DATABASE
Sheet: 1 OF 1
Drawing No: 0000000